

型枠躯体平米数集計表（工区別/部位別）

工事名 KMTマンション新築工事

2016年 7月13日

単位 m² Page. 1

階層	部位	1工区	2工区	3工区	合計	m ³
基礎	柱	31.810	6.214	17.927	55.951	17.570
	梁	803.276	234.939	626.659	1,664.874	392.072
	壁	12.028	22.289	3.092	37.409	3.080
	ベース	687.846	69.496	254.997	1,012.339	455.064
	布ベース	11.548	8.898	1.894	22.340	8.072
	耐圧盤	8.158	1.166		9.324	5.168
	小計	1,554.666	343.002	904.569	2,802.237	881.026
1F	柱	184.246	29.162	99.827	313.235	82.874
	梁	173.812	60.145	97.092	331.049	81.907
	壁	361.126	299.119	332.219	992.464	83.667
	手摺	29.055	25.558	27.278	81.891	4.837
	スラブ	343.423	190.168	199.290	732.881	151.110
	階段	37.957		19.627	57.584	5.060
	小計	1,129.619	604.152	775.333	2,509.104	409.455
2F	柱	149.212	23.898	77.485	250.595	64.847
	梁	164.859	58.770	86.210	309.839	81.237
	壁	406.975	222.056	339.306	968.337	77.588
	手摺	10.596	8.024	10.010	28.630	0.667
	スラブ	336.303	187.629	197.308	721.240	145.160
	階段	56.352		41.318	97.670	10.271
	小計	1,124.297	500.377	751.637	2,376.311	379.770
3F	柱	149.212	23.898	77.485	250.595	64.847
	梁	164.859	58.770	86.210	309.839	81.237
	壁	406.975	222.056	339.306	968.337	77.588
	手摺	10.596	8.024	10.010	28.630	0.667
	スラブ	336.303	187.629	197.308	721.240	145.160
	階段	56.352		41.318	97.670	10.271
	小計	1,124.297	500.377	751.637	2,376.311	379.770
4F	柱	149.212	23.898	77.485	250.595	64.847
	梁	164.859	58.770	86.210	309.839	81.237

型枠躯体平米数集計表（工区別/部位別）

工事名 KMTマンション新築工事

2016年 7月13日

単位 m² Page. 2

階層	部位	1工区	2工区	3工区	合計	m ³
4F	壁	406.975	222.056	339.306	968.337	77.588
	手摺	10.596	8.024	10.010	28.630	0.667
	スラブ	336.303	187.629	197.308	721.240	145.160
	階段	56.352		41.318	97.670	10.271
	小計	1,124.297	500.377	751.637	2,376.311	379.770
5F	柱	143.058	22.956	75.061	241.075	61.114
	梁	163.933	59.068	85.921	308.922	80.611
	壁	409.042	223.514	340.818	973.374	77.927
	手摺	10.596	8.024	10.010	28.630	0.667
	スラブ	337.804	188.724	198.134	724.662	145.863
	階段	56.352		41.318	97.670	10.271
	小計	1,120.785	502.286	751.262	2,374.333	376.453
6F	柱	143.250	23.028	75.253	241.531	61.114
	梁	164.339	59.269	86.326	309.934	80.611
	壁	406.604	223.589	340.818	971.011	75.489
	手摺	10.596	8.024	10.010	28.630	0.667
	スラブ	337.804	188.724	198.134	724.662	145.863
	階段	56.352		41.318	97.670	10.271
	小計	1,118.945	502.634	751.859	2,373.438	374.015
7F	柱	143.250	23.028	75.253	241.531	61.114
	梁	164.339	59.269	86.326	309.934	80.611
	壁	406.604	223.589	340.818	971.011	75.489
	手摺	10.596	8.024	10.010	28.630	0.667
	スラブ	337.804	188.724	198.134	724.662	145.863
	階段	56.352		41.318	97.670	10.271
	小計	1,118.945	502.634	751.859	2,373.438	374.015
8F	柱	143.742	23.220	75.745	242.707	61.114
	梁	160.907	58.255	85.670	304.832	77.802
	壁	404.167	223.661	340.818	968.646	73.052
	手摺	10.596	8.024	10.010	28.630	0.667

型枠躯体平米数集計表（工区別/部位別）

工事名 KMTマンション新築工事

2016年 7月13日

単位 m² Page. 3

階層	部位	1工区	2工区	3工区	合計	
					m ²	m ³
8F	スラブ	339.659	189.939	199.174	728.772	146.689
	階段	56.352		41.318	97.670	10.271
	小計	1,115.423	503.099	752.735	2,371.257	369.595
9F	柱	136.922	22.311	73.050	232.283	57.046
	梁	162.257	58.312	86.572	307.141	78.268
	壁	406.727	228.011	339.789	974.527	73.452
	手摺	10.596	8.024	10.010	28.630	0.667
	スラブ	339.970	190.704	199.271	729.945	146.920
	階段	56.352		41.318	97.670	10.271
	小計	1,112.824	507.362	750.010	2,370.196	366.624
10F	柱	137.072	22.371	73.200	232.643	57.046
	梁	160.305	57.700	86.033	304.038	76.842
	壁	406.710	224.842	342.750	974.302	73.435
	手摺	10.596	8.024	10.010	28.630	0.667
	スラブ	340.915	191.317	199.812	732.044	147.339
	階段	56.352		41.318	97.670	10.271
	小計	1,111.950	504.254	753.123	2,369.327	365.600
11F	柱	137.132	22.426	73.298	232.856	57.046
	梁	157.532	56.908	85.023	299.463	75.075
	壁	406.714	224.869	342.750	974.333	73.439
	手摺	10.596	8.024	10.010	28.630	0.667
	スラブ	342.403	192.595	200.574	735.572	148.065
	階段	56.352		41.318	97.670	10.271
	小計	1,110.729	504.822	752.973	2,368.524	364.563
12F	柱	131.264	21.457	71.356	224.077	53.649
	梁	158.938	57.654	85.504	302.096	75.807
	壁	408.540	226.303	343.566	978.409	73.785
	手摺	10.596	8.024	10.010	28.630	0.667
	スラブ	342.475	192.781	200.596	735.852	148.124
	階段	56.352		41.318	97.670	10.271

型枠躯体平米数集計表（工区別/部位別）

工事名 KMTマンション新築工事

2016年 7月13日

単位 m² Page. 4

階層	部位	1工区	2工区	3工区	合計	m ³
12F	小計	1,108.165	506.219	752.350	2,366.734	362.303
13F	柱	131.264	21.457	71.356	224.077	53.649
	梁	158.938	57.654	85.504	302.096	75.807
	壁	408.540	226.303	343.566	978.409	73.785
	手摺	11.010	8.024	15.350	34.384	1.081
	スラブ	342.475	192.781	200.596	735.852	148.124
	階段	55.691		40.912	96.603	10.006
	小計	1,107.918	506.219	757.284	2,371.421	362.452
14F	柱	147.760	21.855	75.685	245.300	63.081
	梁	159.538	49.352	85.100	293.990	76.976
	壁	477.269	264.264	397.310	1,138.843	87.092
	手摺	9.580	7.600	8.700	25.880	0.776
	特殊手摺	76.058	21.519	63.058	160.635	15.508
	スラブ	359.609	207.906	210.970	778.485	154.892
	柱止め	7.556	2.273	6.127	15.956	
	小計	1,237.370	574.769	846.950	2,659.089	398.325
合計	17,320.240	7,562.58311	555.210	36,438.040	6,143.735	